

Ocelová konstrukce + lavičky (14 ks) - výkaz materiálu

průřez	m (m²)	kg/m (m²)	kg	materiál
HR200x100x5	16,30	21,63	352,60	S 235
HR100x80x5	161,70	13,45	2174,87	S 235
HR100x60x5	11,03	10,96	120,88	S 235
HR80x40x2	130,20	3,67	477,31	S 235
L80x80x8	30,52	9,63	293,91	S 235
L50x50x5	53,20	3,77	200,56	S 235
L100x100x3	122,10	4,71	575,09	S 235
TRø48,3x4	14,50	4,37	63,37	S 235
P8	2,10	78,50	164,85	S 237
SOUČET:			4423,44 kg	
15% rezerva na prořez			663,52 kg	
CELKEM:			5087,0 kg	
Svařovaná síť	410,00	5,27	2159,47	S 235